Standard Operating Procedure: Abnormal Discharge Pressure Response

Document ID:	SOP-OPS-201	**Effective Date:**	2026-08-01
Revision:	3.0	**Classification:**	CONFIDENTIAL - STRICT PROPRIETARY
Department:	Operations CDU-4	**Site Location:**	Jamnagar Refinery Complex (JRC)

1. Purpose

Establishes immediate operator response upon encountering abnormal discharge pressure excursions above approved operating limits (e.g. P-102 pressure exceeding 40.0 bar).

2. Step-by-Step Procedure

1. Verify true hydraulic pressure against local mechanical Bourdon gauge PG-102.
2. If PT-102 reads > 40.0 bar, immediately open minimum flow bypass PCV-102 by 15%.
3. Align standby pump P-101 and prepare for rapid changeover.
4. If casing vibration VT-102A exceeds 5.0 mm/s, initiate controlled emergency stop of motor M-102.