Standard Operating Procedure: Centrifugal Pump Cavitation Mitigation

Document ID:	SOP-OPS-203	**Effective Date:**	2026-08-01
Revision:	2.0	**Classification:**	CONFIDENTIAL - STRICT PROPRIETARY
Department:	Operations & Maintenance	**Site Location:**	Jamnagar Refinery Complex (JRC)

1. Purpose

Action plan for eliminating hydraulic cavitation rumbling and impeller vapor collapse on hydrocarbon transfer pumps.

2. Step-by-Step Procedure

1. Confirm suction filter differential pressure across basket strainer.
2. Increase suction vessel liquid level setpoint by 10% to improve NPSH available.
3. Throttle pump discharge control valve to reduce operating capacity.
4. If cavitation persists > 10 minutes, swap to standby pump to avoid impeller erosion.