# SOP — Medium-Voltage Motor Inspection

Document ID: APEL-SOP-MNT-212 | Owner: Electrical | Revision: 4.8

This page defines the task-specific controls for preparation.

## Preparation

• Verify electrical isolation.

• Review previous test results.

• Confirm test-equipment calibration.

• Check permit.

# Mechanical checks

This page defines the task-specific controls for mechanical checks.

## Mechanical checks

- Terminal box
- Cable glands
- Cooling path
- Coupling guard
- Foundation bolts
- Bearing housing

# Electrical tests

This page defines the task-specific controls for electrical tests.

## Electrical tests

- Insulation resistance
- Polarization index
- Winding resistance
- Earth continuity
- Protection trip verification

# Escalation

This page defines the task-specific controls for escalation.

## Escalation

- Unexpected deterioration
- Moisture ingress
- Winding imbalance
- Protection malfunction

# Record

This page defines the task-specific controls for record.

## Record

- Motor ID
- Instrument ID
- Ambient temperature
- Measured values
- Technician
- Reviewer